



Working at Heights Policy

Contents

[Statement of intent](#)

1. [Legal framework](#)
2. [Definition](#)
3. [Working at heights procedure](#)
4. [Risk assessment](#)
5. [Control measures](#)
6. [Training](#)
7. [Circulation](#)
8. [Monitoring and review](#)

Appendices

- a) [Annual Acknowledgement Statement](#)
- b) [Approved List of Working at Height Activities](#)

Statement of intent

At **The Arthur Terry Learning Partnership (ATLP)**, we recognise that there may be an increased risk to the health and safety of employees when working at heights. This policy has been established to identify risks and manage the risks accordingly.

The school has a duty under the Health and Safety at Work etc. Act 1974 and The Management of Health and Safety at Work Regulations 1999, to ensure, as far as is reasonably practicable, the health, safety and welfare of employees. The school also has obligations under The Work at Height Regulations 2005 (as amended).

Within this policy, 'working at height' refers to situations where staff, in the course of their duties, work at heights and are physically isolated from colleagues, possibly without immediate access to assistance.

1. Legal framework

1.1. This policy has due regard to relevant legislation, including, but not limited to the following:

- The Health and Safety at Work etc. Act 1974
- The Work at Height Regulations 2005 (as amended)

2. Definition

2.1. **ATLP** adopts the definition of the HSE, which defines work at heights as any place where, if there were no precautions in place, a person could fall a distance liable to cause personal injury or death.

3. Working at heights procedure

3.1. The **ATLP Estates Manager** is responsible for ensuring suitable procedures are in place for undertaking risk assessments for all situations requiring work at height. These procedures must ensure that all involved are aware of the precautions and methods of work to be followed, including emergency action to be taken if necessary.

3.2. Working at height should be avoided, where it is practicable to do so, but where work at height cannot be avoided, the risk and consequences of falls should be prevented, using either an existing place of work that is already safe or the right type of equipment. This includes:

- Taking into account weather conditions that could compromise safety.
- Undertaking as much work as possible from the ground.
- Checking that the place where work at height is to be undertaken is safe. Each place where people will work at height needs to be checked each time, before use.
- Preventing materials or objects from falling or, if it is not reasonably practicable to do so, taking suitable and sufficient measures to make sure no one can be injured.
- Ensuring that workers can get safely to and from where they work at height.
- Ensuring equipment is suitable, stable and strong enough for the job, maintained and checked regularly.
- Storing materials and objects safely to ensure they won't cause injury if they are disturbed or collapse.
- Workers ensuring that they don't overload or overreach themselves when working at height.
- Taking precautions when working on or near fragile surfaces.
- Considering emergency evacuation and rescue procedures.

3.3. An approved list of work at height activities will be established, outlining situations where work at height may be authorised, and the necessary precautions and work methods to be followed.

- 3.4. Providing the activity is on the approved list, work at height may be deemed 'authorised'.
- 3.5. Unless explicitly stated on the approved list, work at height must only be undertaken following authorisation from the **ATLP Estates Manager**.
- 3.6. It is the responsibility of the individual concerned to ensure all necessary precautions and methods are adhered to at all times, in accordance with their instructions and training.
- 3.7. Any person, who becomes aware of circumstances involving work at height, where the existing control methods are ineffective, must inform the **ATLP Estates Manager** as soon as possible.
- 3.8. Risk assessments must cover all work currently undertaken at heights (or proposed to be), where the risk may be increased by the work activity itself, or the lack of available assistance should something go wrong. Once relevant tasks are identified, the following must be considered:
 - Plant and equipment: Plant and equipment used by individuals working at height will be assessed for suitability and safety.
 - Access and egress: Some work at height may require access to locations that are difficult to access or egress. Assessments will consider whether these tasks are safe.
 - Lone working: Work at height will not be undertaken when working alone.
- 3.9. Work equipment should be assembled and/or installed according to the manufacturer's instructions and in keeping with industry guidelines.
- 3.10. Where the safety of the work equipment depends on how it has been installed and/or assembled, the **Site Supervisor** should ensure it is not used until it has been inspected in that position by a competent person.
- 3.11. Any equipment exposed to conditions that may cause it to deteriorate, and result in a dangerous situation, should be inspected at suitable intervals appropriate to the environment and use.
- 3.12. A record will be maintained of any inspection for types of work equipment, including guard rails, toe-boards, barriers or similar collective means of protection, and working platforms, both fixed and mobile.
- 3.13. Working platforms used for construction work and from which a person could fall more than two metres must be inspected:
 - After assembly/installation in any position.
 - After any event liable to have affected its stability.
 - At intervals not exceeding seven days.

- 3.14. Where it is a mobile platform, a new inspection and report is not required every time it is moved to a new location on the school/academy premises.
- 3.15. Any equipment, such as a mobile elevating work platform (MEWP), which has come from an external supplier, must be accompanied by a clear indication to everyone involved, when the last thorough examination has been carried out.

4. Risk assessment

- 4.1. The school's risk assessment will include the following considerations:
 - Safety of the pupils, staff, visitors, contractors and the general public.
 - Hazardous nature of any general work at height on the site (i.e. environmental conditions).
 - Required competency level of staff to undertake work at height.
 - Required level of competence and ability to use access equipment.
 - Required level of supervision.
 - The safest equipment to use on site.
 - The condition of access equipment and its maintenance.
 - Other methods of safe access for higher risk or time-consuming jobs at height.

5. Control measures

- 5.1. In order to manage general risks, the following control measures have been put in place. Members of staff working at height must:
 - Not undertake work for which they are not trained.
 - Take reasonable care of their health and safety.
 - Not put themselves in danger.
 - Know, and follow, safe working procedures.
 - Never rush or cut corners.
 - Follow reasonable targets.
 - Stop for regular breaks and, if possible, change activity after prolonged periods.
 - Inform the **ATLP Estates Manager** of any relevant medical conditions.
 - Inform the **ATLP Estates Manager** of any hazards or accidents encountered.
- 5.2. The following communication procedures will also be put in place.
 - Carry a mobile telephone at all times when working at height.
 - The worker will inform someone when they are working at height, how long they will be, and when they expect to be finished.
 - In the event that a worker has an accident or falls into difficulties, they are to use their mobile telephone to contact the headteacher, their nominated person, or the emergency services.
- 5.3. First aid kits will be made available throughout the premises. There locations will be communicated to all members of staff.

6. Training

- 6.1. The **ATLP Estates Manager** will ensure that only individuals with sufficient skills, knowledge and experience are employed to perform a task at height, providing, where necessary, the appropriate training by an accredited trade organisation.
- 6.2. Where staff members are currently undergoing training, they should work under the supervision of somebody competent to work at heights.
- 6.3. Where a working at height activity is low-risk and of a short duration, competence requirements may be no more than making sure an employee receives instruction on how to use the equipment and appropriate on-the-job training.
- 6.4. Where a member of staff finds that they are required to use an item of access equipment on which they have not had instruction/training, or where they are unsure of correct or safe use, then they are to contact the **ATLP Estates Manager** prior to use.
- 6.5. The **ATLP Estates Manager** will maintain an up-to-date record of all instruction and training given to staff members.
- 6.6. Refresher training will be provided every three years.

7. Circulation

- 7.1. This policy will be circulated to every staff member working at height, who shall annually sign a statement which affirms that he/she has:
 - Received a copy of the policy.
 - Has read and understood the policy.
 - Has agreed to comply with the policy.
- 7.2. This policy will be included in the publication scheme on the school's website

8. Monitoring and review

- 8.1. The **ATLP Head of Estates** will be responsible for reviewing this policy annually.